



MINING SECTOR, CEMENT SILO - ORIENTALE REGION, DEMOCRATIC REPUBLIC OF CONGO



TRANSEAST SCOPE OF WORK

- Establish appropriate trailer combination
- Heavy lift crew to plan load & transport the cement silo currently on site to new position within the mine site.
- Submit Method Statement to client.
- Establish route & site survey. Where applicable bridge calculations, turning radiuses, stability calculations.
- Risk analysis and tool box talks to be documented.
- Jack up silo and position Scheuerle modular underneath.
- Lash and move under Transeast escort.
- Client to arrange for off loading and positioning into final position.

CARGO DETAILS

Mass: 30 mt

Length: 19,000 mm

Width: 7,000 mm

EQUIPMENT

1 x 360 HP MAN 8x8.

Scheuerle K25 / 2 file modular/ 9 line modular.

Enerpac hydraulic equipment.

